



# TECHNICAL GUIDANCE

For measurement of all kinds of Gas flow

## TH series THERMAL FLOWMETER

### GENERAL

**TH series THERMAL FLOWMETER** is a flowmeter for gas flow measurement. Based on Tokyo Keiso's original theory and measuring principle, the velocity of various kinds of gases are measured by thermal principle. **TH** can cover from very slow velocity to high velocity that offers very wide range ability compared to other methods of velocity detection of Orifice, Vortex etc.

Various types of detectors and converters are available to meet variety of applications and functional requirements.



### FEATURES

#### High accuracy even in very low flow rate

The thermal flow meter maintains  $\pm 1\%$  F.S.<sup>\*1</sup> of accuracy rating even in such a low flow rate corresponding to 0 to 0.5 m/sec. flow velocity.

#### Extremely low pressure loss

The thin cylindrical shape of sensor is effective in minimising line pressure loss.

#### Long life

Long term running is guaranteed by the provision of a detector without moving parts and of a converter with a highly reliable circuit.

#### Free from line pressure fluctuation

Thanks to basic operational principle, TH Thermal Flowmeter is not affected by a change of a pressure of the gas.

#### Negligible influence of gas temperature

In normal usage, gas temperature fluctuation may cause such slight change on output as to be negligible and may be ignored. When gas temperature varies widely during operation and very accurate flow rate is required, temperature compensation function is available.

(Not applicable for TR-1000 converter)

#### Mass flow

Mass flow is obtained by measuring gas temperature and computing it by temperature compensation circuit.

#### Applicable to various kinds of gases

Based on well analyzed heat conduction mechanism of thin metal tube, applications for gases do not require actual flow rate calibration so long as the physical characteristics are properly specified.

#### Cost effectiveness

Even in large pipe size application, the only price increasing factor is thin lead pipes of the detector, So the instrument, as a whole, provides excellent cost effectiveness.

#### Wide variation of converter unit

To meet applications and requirements, 4 different types of converter unit are ready to choose.

#### High and low temperature version

This version is available for the measurement of gases from  $-196^{\circ}\text{C}$  to  $+550^{\circ}\text{C}$ .

Namely, this flowmeter can be used for the applications with which the conventional one could not comply.

### RECOMMENDED APPLICATION

#### Semiconductor Gas supply lines

#### Medical Oxygen supply facilities

#### Air conditioning

#### Utility Gas supply lines in industries

#### High Temperature Dry Air lines

#### Combustion Gas lines

#### Low Pressure and Low Velocity Gas lines

#### Incineration Facilities lines

#### Electric Power Plant lines

#### Flow Rate Measurement System for Automobile Examination lines


#### Other Gas supply applications

\*1 Accuracy of TR-1000 and TRX-5000 converters are  $\pm 2.0\%$  F.S.


# THERMAL FLOWMETER

## LINE UP OF TH THERMAL FLOWMETERS

Widely prepared Line-up of TH Thermal Flowmeters covers various applications and requirements.

<b>GENERAL PURPOSE SENSORS</b>	 <p><b>TH-1100</b> Insertion type</p>  <p><b>TH-1200</b> Flange type</p>  <p><b>TH-1400</b> Variable Length Insertion type</p>
<b>SENSOR WITH PURGE FUNCTION</b>	 <p><b>TH-1100-SP</b> Insertion type (Max. Temp. 240°C)</p>  <p><b>TH-3200-SP</b> Insertion type (Max. Temp. 360°C)</p>
<b>HIGH AND LOW TEMP VERSION</b>	 <p><b>TH-3100, TH-3200, TH-3300</b> Insertion type</p>
<b>HIGH QUALITY SENSORS</b>	 <p><b>TH-1100-HQ</b> Insertion type</p>  <p><b>TH-1500-HQ</b> In-line welding type</p>
<b>CONVERTERS FOR GENERAL PURPOSE SENSORS AND HIGH QUALITY SENSORS</b>	 <p><b>TR-1000</b> General, Panel mount</p>  <p><b>TRX-5000</b> General, Field mount</p>
	 <p><b>TRX-700</b> Intelligent, Panel mount</p>  <p><b>TRX-900</b> Intelligent, Field mount</p>

## COMBINATION EXAMPLES



## OPERATION PRINCIPLE

When a heated metallic tubule is located in a gas flow path, the heat of the tubule is removed by the velocity. The lost heat is described by the following formula:

$$H = f (\rho U \times \Delta T)$$

Where **H** : Lost heat    **ρ** : Density

**U** : Velocity    **ΔT** : Difference of temperature gas and heated tubule

On the contrary, the generated heat on the tubule is described by the function of supplied voltage and current onto the tubule,

$$W = f (V \times I)$$

Where **W** : Generated heat

**V** : Supplied voltage    **I** : Supplied current

When the heated tubule is in balanced condition, the lost heat and generated heat are equal, and if the **ΔT** is controlled electrically, the velocity is calculated from the figures of supplied voltage and current


$$\rho U = f (V \times I)$$

The total flow rate is calculated from the velocity and the cross section area of flow path:

$$Q = \rho U \times A$$

Where **Q** : Flow rate    **U** : Average velocity

**A** : Cross section area of flow path



# TH THERMAL FLOWMETER

## FOR GENERAL PURPOSE

### TH-1100

#### OUTLINE

TH-1100 is an insertion type detector of light weight and small size for easy installation.

Low cost measurement possible even for large size line. Besides normal pipe line, gas flow measurement in square duct also possible.




#### MODEL CODE

TH-11	Model code					Description
	①	②	—	③	④	⑤
① Process pipe size	5					50 mm (2")
	6					65 mm (2-1/2")
	7					80 mm (3")
	8					100 mm (4")
	9					125 mm (5")
	A					150 mm (6")
	B					200 mm (8")
	C					250 mm (10")
	D					300 mm (12")
	E					350 mm (14")
	F					Others
② Sensor material	1					304SS
	2					316SS
	3					316LSS
	F					Special
③ Process connection	1					32A JIS10K flange
	2					1-1/4" ANSI 150 flange
	F					Others
④ L length	1					Standard
	F					Special
⑤ Special						Standard type (Blank)
						X Terminal box type (Make it blank if in case of connector type.)
						E EP grade: Electrolytic polishing (Except sensor part)
						B BA grade: Electrolytic polishing (Except sensor part)

#### STANDARD SPECIFICATION

Type	Insertion type (Std. 32 mm JIS10K flange)	
Available size	50 mm (2") to 1500 mm (60") * Up to 1500 mm size available on request.	
Measuring range	Min.	Air : 0 to 0.5 m/s (nor)
	Max.	Air : 0 to 130 m/s (nor)
Max. Op. Press	1.0 MPa	
Max. Op. Temp. segment	80°C / 180°C / 240°C	
Material	Sensor	316SS
	Detector	304SS, 316SS, 316LSS
	Seal	Viton, Others Construction
Water proof	IP65 equiv.	
Required upstream straight run (Recommendation)	20D (D: Inside diameter)	

#### DIMENSION



Process pipe size (mm)	L (mm)
50 to 150	182
200 to 250	200
300 to 350	250
More than 400	Consult factory for details

**TH-1200****OUTLINE**

TH-1200 is a flange connected detector.

Perfect fit on process piping.



6 sizes from 50 mm to 150 mm available.

**MODEL CODE**

TH-12	Model code				Description
	①	②	③	④	
① Process pipe size	5				50 mm (2")
	6				65 mm (2-1/2")
	7				80 mm (3")
	8				100 mm (4")
	9				125 mm (5")
	A				150 mm (6")
② Sensor material	1				304SS
	2				316SS
	3				316LSS
	F				Special
③ Process connection	3				JIS10K flange
	4				ANSI 150 flange
	F				Others
⑤ Special	Standard type (Blank)				
	X	Terminal box type (Make it blank if in case of connector type.)			
	S	With straightener built in			
	E	EP grade: Electrolytic polishing (Except sensor part)			
	B	BA grade: Electrolytic polishing (Except sensor part)			
	T	With tap for thermometer installation (Rc1/8)			

**STANDARD SPECIFICATION**

Type	Flange ended	
Available size	50 mm (2") to 150 mm (6")	
Measuring range	Min.	Air : 0 to 0.5 m/s (nor)
	Max.	Air : 0 to 130 m/s (nor) (Without straightener)
	Max.	Air : 0 to 40 m/s (nor) (With straightener)
Max. Op. Press.	1.0 MPa	
Max. Op. Temp. segment	80°C / 180°C	
Material	Sensor	316SS
	Detector	304SS, 316SS, 316LSS
	Seal	Viton, Others Construction
Water proof	IP65 equiv.	
Required upstream straight run (Recommendation)	20D (Without straightener) (D: Inside diameter) 3D to 5D (With straightener)	

**DIMENSION****Straightener**


Process pipe size	50 mm	65 mm	80 mm	100 mm	125 mm	150 mm
L	80	90	100	130	150	190

**TH-1400****OUTLINE**

TH-1400 is a variable length insertion detector provided for checking flow profile in pipe line. Gate valve (customer's supply) can be added for easy maintenance without interrupting process operation.

**MODEL CODE**

TH-14	Model code					Description
	①	②	—	③	④	⑤
① Process pipe size	5					50 mm (2")
	6					65 mm (2-1/2")
	7					80 mm (3")
	8					100 mm (4")
	9					125 mm (5")
	A					150 mm (6")
	B					200 mm (8")
	C					250 mm (10")
	D					300 mm (12")
	E					350 mm (14")
② Sensor material	F					Others
	1					304SS
	2					316SS
	3					316LSS
③ Process connection	F					Special
	1					40A JIS10K flange
	2					1-1/2" ANSI 150 flange
④ L length	F					Others
	1					Standard
⑤ Special	F					Special
						Standard type (Blank)
						X Terminal box type (Make it blank if in case of connector type.)
						E EP grade: Electrolytic polishing (Except sensor part)
						B BA grade: Electrolytic polishing (Except sensor part)

**DIMENSION****STANDARD SPECIFICATION**

Type	Insertion type (Std. 40 A JIS10K flange)	
Available size	50 mm (2") to 1500 mm (60") * Up to 1500 mm size available on request.	
Measuring range	Min.	Air : 0 to 0.5 m/s (nor)
	Max.	Air : 0 to 130 m/s (nor)
Max. Op. Press.		1.0 MPa
Max. Op. Temp. segment		80°C / 180°C
Material	Sensor	316SS
	Detector	304SS, 316SS, 316LSS
	Seal	Viton, Teflon Others
Water proof	IP65 equiv.	
Required upstream straight run (Recommendation)	20D (D: Inside diameter)	

Process pipe size (mm)	L (mm)
50 to 150	182
200 to 250	200
300 to 350	250
More than 400	Consult factory for details

**TH-1700****OUTLINE**

TH-1700 series can be manufactured from the nominal diameter 15 mm to 50 mm.

The process connection is only flange connection type.


5 sizes from 15 mm to 50 mm available.

**MODEL CODE**

TH-17	Model code					Description
	①	②	③	④	⑤	
① Process pipe size	1					15 mm (1/2")
	2					20 mm (3/4")
	3					25 mm (1")
	4					40 mm (1 1/2")
	5					50 mm (2")
② Operating Temp. range	1					Std. / Temp. range (0 to 80°C)
	2					High Temp. / Temp. range (0 to 180°C)
	7					Low Temp. / Protected against dew condensation (-20 to + 80°C)
③ Sensor material	4					304SS / SCS14
	5					316SS / SCS14
	6					316LSS / SCS16
④ Process connection	1					JIS10K flange
	F					Others
⑤ Special						Standard type (Blank)
	E					EP grade: Electrolytic polishing (Except sensor part)
	B					BA grade: Electrolytic polishing (Except sensor part)
	T					With tap for thermometer installation (Rc1/8)
C						Connector type (For built-in type)

**STANDARD SPECIFICATION**

Type	Flange ended
Available size	15 mm (1/2") to 50 mm (2")
Measuring range	Min.
	Air : 0 to 0.5 m/s (nor)
Max. Op. Press.	1.0 MPa
Max. Op. Temp. segment	80°C / 180°C
Material	Sensor
	316SS
	Detector
Water proof	SCS14, SCS16, 304SS, 316SS, 316LSS
	Viton, Others Construction
Required upstream straight run (Recommendation)	IP65 equiv.
	20D (D: Inside diameter)

**DIMENSION****Standard type**

Size Dimension	L1	L2	J
15 mm			15A JIS10K flange
20 mm	180	90	20A JIS10K flange
25 mm			25A JIS10K flange
40 mm	300	150	40A JIS10K flange
50 mm			50A JIS10K flange

**With tap for thermometer installation type**

Size Dimension	L1	L2	J
15 mm			15A JIS10K flange
20 mm	270	90	20A JIS10K flange
25 mm			25A JIS10K flange
40 mm	330	150	40A JIS10K flange
50 mm			50A JIS10K flange

**TH-1800****OUTLINE**

TH-1800 has a built-in flow straightener which eliminates the necessity of straight run upstream and downstream.

(Slight pressure loss is created by this built-in flow straightener. Consult factory when process pressure is very low.)

**MODEL CODE**

TH-18	Model code					Description	
	①	②	—	③	④	⑤	
① Process pipe size	1						15 mm (1/2")
	2						20 mm (3/4")
	3						25 mm (1")
	4						40 mm (1 1/2")
	5						50 mm (2")
② Operating Temp. range	1						Std. / Temp. range (0 to 80°C)
	2						Temp. range (0 to 180°C)
	7						Low Temp. / Protected against dew condensation (-20 to + 80°C)
③ Sensor material	4						304SS / SCS14
	5						316SS / SCS14
	6						316LSS / SCS16
④ Process connection	1						JIS10K flange
	2						JIS Rc screw (3/8")
	3						JIS Rc screw (1/2")
	4						JIS Rc screw (3/4")
	5						JIS Rc screw (1")
	F						Others
⑤ Special							Standard type (Blank)
							E EP grade: Electrolytic polishing (Except sensor part)
							B BA grade: Electrolytic polishing (Except sensor part)
							T With tap for thermometer installation (Rc1/8)
							C Connector type (For built-in type)

\*Available process connection and sizes


Nominal diameter \ Connection	15 mm	20 mm	25 mm	40 mm	50 mm
Flange	○	○	○	○	○
Rc3/8	○	×	×	×	×
Rc1/2	○	○	×	×	×
Rc3/4	×	○	○	×	×
Rc1	×	×	○	×	×

Note) ○: Producible ×: Unproducible

**STANDARD SPECIFICATION**

Type	Flange or Screw ended
Available size	15 mm (1/2") to 50 mm (2")
Measuring range	Min.
	Air : 0 to 0.5 m/s (nor)
Max. Op. Press.	Max.
	Air : 0 to 45 m/s (nor)
Max. Op. Temp. segment	80°C / 180°C
Material	Sensor
	316SS
	Detector
Water proof	SCS14, SCS16, 304SS, 316SS, 316LSS
	Viton, Others Construction
Required upstream straight run (Recommendation)	IP65 equiv.
	3D to 5D (D: Inside diameter)

## DIMENSION



Standard type

Size Dimension	L1	L2	J	øD	W
15 mm	210	105	Rc3/8 • Rc1/2	ø36	32
	180	90	15A JIS10K flange	—	—
20 mm	250	145	Rc1/2 • Rc3/4	ø36	32
	220	130	20A JIS10K flange	—	—
25 mm	280	170	Rc3/4 • Rc1	ø46	41
	240	150	25A JIS10K flange	—	—
40 mm	280	170	40A JIS10K flange	—	—
50 mm	320	210	50A JIS10K flange	—	—

With tap for thermometer installation type

Size Dimension	L1	L2	J	øD	W
15 mm	300	105	Rc3/8 • Rc1/2	ø36	32
	270	90	15A JIS10K flange	—	—
20 mm	340	145	Rc1/2 • Rc3/4	ø36	32
	310	130	20A JIS10K flange	—	—
25 mm	370	170	Rc3/4 • Rc1	ø46	41
	330	150	25A JIS10K flange	—	—
40 mm	350	170	40A JIS10K flange	—	—
50 mm	390	210	50A JIS10K flange	—	—

**SENSOR WITH PURGE FUNCTION****TH-1100-SP / TH-3200-SP****OUTLINE**

TH-1100-SP / TH-3200-SP are the sensors with purge function. Purged gas prevents the dust to the sensor section from adhering and removes the adhered dust, resulting in performing the stable measurement of flow rate.

Note: Regarding the adhesive dust, it may be that the sufficient effect can not be obtained.

**MODEL CODE**


TH-11 TH-32	Model code					Description
	①	②	③	④	⑤	
① Process pipe size	A					150 mm (6")
	B					200 mm (8")
	C					250 mm (10")
	D					300 mm (12")
	E					350 mm (14")
	F					Others
② Sensor material	1					304SS
	2					316SS
	3					316LSS
	F					Special
③ Process connection	1					65A JIS10K flange
	F					Others
④ L length	1					Standard
	F					Special
⑤ Special						Standard type (Blank)
	C					Connector type (Make it blank if in case of terminal box type.)

**STANDARD SPECIFICATION**


Model	TH-1100-SP	TH-3200-SP
Type	Insertion type (Std. 65A JIS10K flange)	
Available size	150 mm (6") to 1500 mm (60") * Up to 1500 mm size available on request.	
Measuring range	Min. Max.	Air : 0 to 0.5 m/s (nor) Air : 0 to 5 m/s (nor) Air : 0 to 75 m/s (nor)
Max. Op. Press.		1.0 MPa 0.1 MPa
Max. Op. Temp. segment		80°C / 240°C 360°C
Material	Sensor	316SS
	Detector	304SS, 316SS, 316LSS
	Seal	Viton, Others
Water proof		IP65 equiv.
Required upstream straight run (Recommendation)		20D (D: Inside diameter)

**DIMENSION**

TH-1100-SP



TH-3200-SP



Process pipe size (mm)	L (mm)
150	182
200 to 250	200
300 to 350	250

**HIGH AND LOW TEMP. VERSION****TH-3100 / TH-3200 / TH-3300****OUTLINE**

HIGH AND LOW TEMP. VERSION is available for TH series THERMAL FLOWMETER.

Low temp. version covers upto minus 196°C and High temp. version covers upto plus 550°C.

HIGH AND LOW TEMP. VERSION will be used together with TRX-5000 type converter.

**MODEL CODE**

TH—3		Model code					Description	
① Type	①	②	③	—	0	④	⑤	
	1							For high temp. Max. 0.1 MPa press.
	2							For high temp. Max. 0.1 MPa press.
	3							For low temp. Max. 0.1 MPa press.
② Process pipe size	6							65 mm (2-1/2") *TH-3200/TH-3300
	7							80 mm (3")
	8							100 mm (4")
	9							125 mm (5")
	A							150 mm (6")
	B							200 mm (8")
	C							250 mm (10")
	D							300 mm (12")
	E							350 mm (14")
	F							Others
③ Sensor material	1							304SS
	2							316SS
	3							316LSS
	F							Special
④ Process connection	1							Standard
	F							Special
⑤ L length	1							Standard
	F							Special


**STANDARD SPECIFICATION**

Model		TH-3100	TH-3200	TH-3300
Insertion type				
Type		Std. 65 A JIS10K flange	Std. 32 A JIS10K flange	
Available size		80 mm (3") to 1500 mm (60")		
Measuring range	Min.	Air : 0 to 5 m/s (nor)		
	Max.	Air : 0 to 75 m/s (nor)		
Max. Op. Press.		1.0 MPa	0.1 MPa	
Max. Op. Temp.		0 to 550°C (for high temp.)		-196 to 0°C (for low temp.)
Material	Sensor	316SS		
	Detector	304SS, 316SS, 316LSS		
Water proof		IP65 equiv.		
Required upstream straight run (Recommendation)		20D (D: Inside diameter)		

**DIMENSION**

- Sensor
- TH-3100

- TH-3200 / TH-3300



Process pipe size (mm)	L (mm)
80 to 150	182
200 to 250	200
300 to 350	250
More than 400	Consult factory for details

Process pipe size (mm)	L (mm)
65 to 150	182
200 to 250	200
300 to 350	250
More than 400	Consult factory for details

**HIGH QUALITY SENSORS****TH-1100-HQ****OUTLINE**

TH-1100-HQ is a insertion type detector. EP polished surface and hermetical sealing have achieved elimination of depositing of particles and low leakage rate.


TH-1100-HQ is suitable for applications with high grade quality control such as gas supply lines in semi-conductor production facilities.

**MODEL CODE**

Model code			Description
TH-11	①	②	
① Process pipe size	5		50 mm
	6		65 mm
	7		80 mm
	8		100 mm
② Sensor material	1		Standard
	F		Special

**DIMENSION****STANDARD SPECIFICATION**

Type	High quality version (Insertion type) (Special flange nozzle)	
Available size	50 mm (2") to 100 mm (4")	
Measuring range	Min.	Air : 0 to 0.5 m/s (nor)
	Max.	Air : 0 to 75 m/s (nor)
Max. Op. Press.	1.0 MPa	
Max. Op. Temp.	120°C (180°C as option)	
Material	Body	316LSS, EP polished Surface roughness Rmax. $\leq$ 0.7μm
	Sensor	316SS, OVAR(Ni,Co alloy) + AL <sub>2</sub> O <sub>3</sub> + Gold brazing + Ni plated, BA treatment
	Seal	Body Teflon coated Metal O ring Sensor 316SS
He leak rate	Max. 1x10 <sup>-10</sup> Pa·m <sup>3</sup> /s	
Construction	Water proof (IP65 equiv.)	
Scope of supply	Standard 1) Sensor 2) Special flange piece (for pipe welding) 3) Metal O ring	
	On request Spacer for installation to pipe by welding	



Size (mm)	Dimension (mm)
	L
50 mm	94
65 mm	94
80 mm	120
100 mm	120

**TH-1500-HQ****OUTLINE**


TH-1500-HQ is a High quality, in-line installatin type detector. Like TH-1500-HQ, EP polished surface and metal sealing have achieved elimination of depositing of particles and low leakage rate and is also suitable for semi-conductor production facilities.

**MODEL CODE**

Model code				Description
TH-15 (① ②) — ③ HQ				
① Process pipe size	1			15 mm
	2			20 mm
	3			25 mm
② Sensor material	1			Standard
	F			Special
③ Process connection	1			Welding type (I fusion face)
	F			Others

**STANDARD SPECIFICATION**

Type	High quality version (Process piping welding type)	
Available size	15 mm (1/2") to 25 mm (1")	
Measuring range	Min.	Air : 0 to 0.5 m/s (nor)
	Max.	Air : 0 to 75 m/s (nor)
Max. Op. Press.	1.0 MPa	
Max. Op. Temp.	120°C (180°C as option)	
Material	Body	316LSS, EP polished Surface roughness Rmax. $\leq$ 0.7 μm
	Sensor	316SS, OVAR (Ni,Co alloy) + Al <sub>2</sub> O <sub>3</sub> + Gold brazing + Ni plated, BA treatment
	Seal	Body Teflon coated Metal O ring Sensor 316SS
He leak rate	Max. 1×10 <sup>-10</sup> Pa·m <sup>3</sup> /s	
Construction	Water proof (IP65 equiv.)	

**DIMENSION**

Size (mm)	Dimension (mm)							
	J	L	H1	H2	H3	PB1	PB2	BH
15 mm	Ø21.7×1.65t	350	20	95	115	30	40	4-M4 (d - 6)
20 mm	Ø27.2×1.65t							
25 mm	Ø34.0×1.65t							

## CONVERTERS FOR GENERAL PURPOSE SENSORS AND HIGH QUALITY VERSION SENSORS

### TR-1000

#### OUTLINE

TR-1000 is the most simple but well accepted converter for TH series Thermal Flowmeters.

You can get flow rate indication by LED and analog output of DC 4 - 20 mA for further recording and / or control purpose. indoor use housing design.

#### MODEL CODE

TR-1	Model code				Description	
	①	②	-	③	④	
① Flow rate indication	0					Not provided
	1					Provided
② Analog output	0					Not provided
	1					Provided (DC4 to 20 mA)
③ Power supply	1					AC 100 V±10%, 50/60Hz
	2					AC 110 V±10%, 50/60Hz
	3					AC 115 V±10%, 50/60Hz
	4					AC 200 V±10%, 50/60Hz
	5					AC 220 V±10%, 50/60Hz
	6					AC 240 V±10%, 50/60Hz
	1					5 m
④ Cable length	2					10 m
	3					15 m
	4					20 m
	5					25 m
	6					30 m
	7					40 m
	8					50 m (max.)
	F					Others


#### STANDARD SPECIFICATION

Connectable Detector	TH-1100, 1200, 1400, 1700, 1800, 1100-HQ, 1500-HQ
Installaton	Panel or rack mount
Construction	Indoor use (IP20 equiv.)
Flow rate indication	Available (3 1/2 digit LED)
Totalization indication	Not available
Analog output	Provided DC 4 to 20 mA, Max.Load 500Ω
Pulse output	Not provided
Temp.compensation	Not provided
Accuracy	±2.0% F.S.
Response time	5 sec (63% step response)
Max. distance to sensor	50 m (max)
Power supply	AC 100, 110, 115, 200, 220, 240V ±10%, 50/60Hz
Power consumption	30 VA
Cable termination	M3 terminal connection
AMB temp.	0 to 50°C
AMB Humidity	10-90% RH (To be free from condensation)
Housing material	SPCC
Approx. weight	3kg




#### DIMENSION

- TR-1000 (Without indicator) Panel cut



- TR-1000 (With indicator)



**TRX-5000****OUTLINE**

TRX-5000 is a converter designed for a water-proof construction thermal flowmeter of field installing type. It can indicate and output flow rate and totalization simultaneously. It is also capable of extending various functions by mounting an option circuit board. Furthermore, a maximum of 16 types of gas substance and their flow rate ranges are programmable in advance.

**MODEL CODE**

Model code				Description
TRX-5		-	-	
Indication	1			Flow rate
	3			Flow rate + Totalization
Output	3			DC 4 to 20 mA + Pulse output
Temperature correction (Input signal)	0			No correction
	1			Resistance temp. sensor (Pt 100Ω)
	2			DC 4 to 20 mA temp.signal
	3			DC 1 to 5 V temp.signal
Power supply	1			AC 100 V±10%
	2			AC 110 V±10%
	3			AC 115 V±10%
	4			AC 200 V±10%
	5			AC 220 V±10%
	6			AC 240 V±10%
Cable length	1			5 m
	2			10 m
	3			15 m
	4			20 m
	5			25 m
	6			30 m
	7			40 m
	8			50 m (max.)
	F			Others
Cable entry	1			G1/2
	F			Others
2" pipe mount fitting	0			Not provided
	1			Provided
Option circuit board (*1)	Purge control input	1		Open collector (Standard)
		2		Contact input (*2)
	Purge output	1		O.C. + Contact output (*3)
		2		O.C. + AC output (*3)
	Contact output	1		Flow switch
		2		Abnormality alarm output
	RS-232C serial output	0		Not provided
		1		Flow rate + Temp. indication

\* 1: In case of not adding option circuit board, description is omitted.


\* 2: In case of manual switch, this is selected.

\* 3: O.C. = Open collector

**STANDARD SPECIFICATION**

Connectable detector	TH-1100 (-HQ) /1200/1400/1500-HQ 1700/1800/3000/1100-SP/3200-SP
Installation	Installation on wall or 2B pipe
Construction	Jet stream-proof type (IP65 equivalent)
Accuracy	±2%F.S. ±1digit / ±2%F.S. (indication/output)
Flow rate indication	5-digit LED (0.000 to 62500) Low cut-off : 2%F.S. (Standard) / 0 to 10%F.S.
Totalization indication*	8-digit LCD (Manual reset) Dropout: 2%F.S. (Standard) / 0 to 10%F.S.
Analog output	DC 4 to 20 mA / Allowable load resistance 500Ω Low cut-off : 2%F.S. (Standard) / 0 to 10%F.S.
Pulse output	Open collector output / DC 35 V/50 mA (max.) Pulse width : 50 to 200 msec (10 msec interval) Standard : 50 msec Pulse rate : 1 to 600 c/min 6 to 36000 c/h
Digital output	9600 bps Protocol : 8N 1 Output : Readings
Contact output of alarm*	SPDT relay contact / AC 125 V / 0.4 A (DC 30 V / 2 A) · Flow switch Action : 100%F.S. (Standard) / 0 to 120%F.S. Hysteresis : 1%F.S. (Standard) / 1 to 10%F.S. · Abnormality alarm output
Temp. correction function*	3-wire type resistance temp. sensor (Pt100Ω) or temp. sensor with analog output (DC 4 to 20 mA or DC 1 to 5 V) is required separately.
Response time	5 seconds (63% step response)
Elect. connection	Pin terminal connector
Power supply	AC100, 110, 115, 200, 220, 240 V. ±10%, 50/60Hz
Power consumption	About 30 W
Housing	Aluminum die cast / Cobalt blue
Dimensions / Weight	206 W × 326 H × 123 D (mm) About 4.5kg
Ambient temp.	-10 to 60°C
Ambient humidity	10 to 90%RH (No dew condensation)

\* In case of adding option specification

**DIMENSION**

**TRX-700 / TRX-900****OUTLINE**

TRX-700 / TRX-900 series are an intelligent type converter for thermal flowmeters. High-precision and high-performance capacities have been achieved by the new design of a signal processing circuit mounting double CPU's.

All the operation factors are handled by the operating keys arranged on the front panel that enables to make settings and alterations in a user-friendly way.

Functions necessary for process monitoring and controlling such as flow rate, totalization and alarm output are all installed as the standard specification.

In addition, data processing with a host computer has made available through serial communication with RS-485 interface.

Easy maintenance with self-diagnosis function

DIN96 × 96 compact housing

Two types available

a) TRX-700 Panel mount type

b) TRX-900 Field mount type (Water proof housing)

**MODEL CODE**

Model code			Description	
TRX-	①	②	③	
① Type	7			DIN 96 × 96 Panel mount type
	9			Water proof housing, Field mount type
② Temperature and pressure correction	0			No correction
	1			Temperature correction
③ Cable length	4			Temp. and Press. correction
	1			5 m
	2			10 m
	3			15 m
	4			20 m
	5			25 m
	6			30 m
	7			35 m
	8			40 m
	9			45 m
	A			50 m
	F			50 m to 100 m *Specify the cable length

**STANDARD SPECIFICATION**

Connectable detector	TH-1100/1100-HQ/1200 1400/1500-HQ/1700/1800
Installation	TRX-700 : Panel mount type (DIN 96 × 96) TRX-900 : Wall or 2B pipe mount type
Construction	TRX-700 : IP20 equiv. (Indoor use) TRX-900 : IP54 equiv. (Field use)
Accuracy	Analog output ±1%F.S. ± 1 digit (Flow rate) Pulse output ±1.05%F.S. ± 1 digit (Totalization)
Analog output	DC 4 to 20 mA / Allowable load resistance 500Ω
Pulse output	Open collector output / DC 35 V/ 50 mA (max.) Pulse width : 50, 100, 200 msec Pulse rate : 0.0 to 600 c/min 0 to 36000 c/h
Contact output of alarm	SPDT relay contact (High alarm/ Low alarm) AC 125 V/0.4 A (DC 20 V/2 A)
Digital output (RS-485)	1200 / 2400 / 4800 / 9600bps (Selectable) ID address : 00 to 99 Protocol : 8N1 Output : Flow rate, totalization, bar graph, temp., pressure, heating current, firmware version, serial No., error message, etc.
Display	Dot matrix LCD, 16 characters × 2 lines With backlight
Indication	Upper section Select one item from flow rate, totalization, temp., Pressure, heating voltage, internal temp. and SPS ripple, or error message.
	Lower section Select one item from bar graph, flow rate, Totalization, temp., pressure and heating current, Or error message.
Maximum number of display digits	Analog output 5 digits (0.000 to 99999) (Flow rate) Pulse output 7 digits (0.00 to 9999999) (Totalization)
Temp. correction function	3-wire type resistance temp. sensor (Pt100 Ω) is required separately.
Pressure correction function	Pressure gauge with DC 4 to 20 mA analog output is required separately. (Used mainly for indication of actual flow rate.)
Response time	3 seconds (63% step response)
Dimensions	96 H × 96 W × 243 D (mm)
Weight	About 1.95kg
Cable length	100 m (max.)
Power supply	AC 90 to 264 V 50/60 Hz
Power consumption	60 W (max.)
Elect. connection	Pin terminal connector
Ambient temp.	0 to 50°C
Ambient humidity	10 to 90% RH (No dew condensation)




TRX-700




TRX-900

## DIMENSION


- TRX-700 (Panel mount type)



- TRX-900 (Wall mount type)



- TRX-900 (2B pipe mount type)







## TH-3200-SP

Unit : m<sup>3</sup>/h(nor)

Gas Size	AIR	N <sub>2</sub>	CO <sub>2</sub>	O <sub>2</sub>	Ar	13A	CH <sub>4</sub>	C <sub>3</sub> H <sub>8</sub>	C <sub>4</sub> H <sub>10</sub>	NH <sub>3</sub>
150 mm	255 to 3815	255 to 3805	345 to 5150	250 to 3715	510 to 7585	165 to 2475	170 to 2500	165 to 2445	135 to 2010	245 to 3635
200 mm	455 to 6805	455 to 6790	615 to 9185	445 to 6625	905 to 13530	295 to 4410	300 to 4465	295 to 4365	240 to 3585	435 to 6480
250 mm	725 to 10830	725 to 10810	975 to 14625	705 to 10550	1440 to 21545	470 to 7025	475 to 7105	465 to 6950	385 to 5710	690 to 10315
300 mm	1045 to 15675	1045 to 15645	1415 to 21165	1020 to 15270	2080 to 31180	680 to 10165	690 to 10285	675 to 10060	555 to 8265	1000 to 14930
350 mm	1315 to 19715	1315 to 19680	1775 to 26620	1285 to 19205	2615 to 39215	855 to 12785	865 to 12935	845 to 12650	695 to 10395	1255 to 18780
400 mm	1750 to 26185	1745 to 26135	2360 to 35350	1705 to 25505	3475 to 52080	1135 to 16980	1145 to 17180	1120 to 16800	920 to 13805	1665 to 24940
450 mm	2240 to 33560	2235 to 33500	3025 to 45310	2180 to 32695	4450 to 66755	1455 to 21770	1470 to 22020	1440 to 21535	1180 to 17695	2135 to 31970
500 mm	2780 to 41680	2775 to 41605	3755 to 56275	2710 to 40605	5530 to 82905	1805 to 27035	1825 to 27350	1785 to 26745	1465 to 21975	2650 to 39700
550 mm	3395 to 50865	3385 to 50770	4580 to 68675	3305 to 49550	6745 to 101170	2200 to 32990	2225 to 33375	2180 to 32640	1790 to 26815	3230 to 48450
600 mm	4040 to 60550	4030 to 60435	5450 to 81745	3935 to 58985	8030 to 120430	2620 to 39270	2650 to 39730	2590 to 38855	2130 to 31920	3845 to 57675
650 mm	4725 to 70850	4715 to 70715	6480 to 95650	4605 to 69015	9395 to 140915	3065 to 45950	3100 to 46490	3035 to 45460	2490 to 37350	4500 to 67485
700 mm	5515 to 82680	5505 to 82525	7445 to 111625	5370 to 80540	10965 to 164445	3575 to 53625	3620 to 54250	3540 to 53055	2910 to 43585	5250 to 78755
750 mm	6365 to 95425	6350 to 95245	8590 to 128830	6200 to 92955	12655 to 189790	4130 to 61890	4175 to 62615	4085 to 61230	3355 to 50305	6060 to 90890
800 mm	7275 to 109080	7260 to 108875	9820 to 147265	7085 to 106260	14465 to 216950	4720 to 70745	4775 to 71575	4670 to 69995	3835 to 57505	6930 to 103900
850 mm	8245 to 123645	8230 to 123415	11130 to 166930	8030 to 120450	16395 to 245925	5350 to 80195	5410 to 81135	5290 to 79345	4350 to 65185	7855 to 117775
900 mm	9275 to 139125	9260 to 138870	12525 to 187830	9035 to 135530	18450 to 276715	6020 to 90235	6090 to 91290	5955 to 89275	4890 to 73345	8835 to 132520
1000 mm	11455 to 171775	11435 to 171455	15465 to 231910	11160 to 167335	22780 to 341650	7430 to 111410	7515 to 112715	7350 to 110225	6040 to 90555	10910 to 163620
1100 mm	13970 to 209550	13945 to 209160	18865 to 282905	13610 to 204130	27785 to 416780	9065 to 135910	9170 to 137500	8965 to 134465	7365 to 110470	13310 to 199600
1200 mm	16655 to 249810	16625 to 249350	22485 to 337285	16225 to 243355	33125 to 498680	10805 to 162025	10930 to 163920	10690 to 160300	8780 to 131695	15865 to 237950
1300 mm	19575 to 293605	19540 to 293065	26430 to 396390	19070 to 286015	38935 to 583965	12700 to 190430	12845 to 192655	12565 to 188405	10320 to 154785	18645 to 279665
1400 mm	22730 to 340940	22690 to 340305	30690 to 460290	22145 to 32125	45210 to 678100	14745 to 221130	14915 to 223715	14585 to 218780	11985 to 179735	21650 to 324750
1500 mm	26120 to 391800	26075 to 391075	35265 to 528960	25445 to 381675	51955 to 779270	16945 to 254120	17140 to 257090	16765 to 251415	13770 to 206555	24880 to 373200

\*Measuring range : 0 to Full scale


Ex) TH-1100 150 mm, Air

Min. measuring range : 0 to 45 m<sup>3</sup>/h (nor)Max. measuring range : 0 to 840 m<sup>3</sup>/h (nor)

## APPLICATION EXAMPLE

Thermal Flowmeter is connected with the special signal cable between sensor and converter. Refer to the following table for details.

- Connection and special signal cable



## SUGGESTIONS

- TH series Thermal Flowmeter is not suitable for the measurement of gases containing condensate and/or sticking contamination. In that case, we can provide air purge system as option. Consult factory for details.
- Specified straight run for upstream and downstream is required for accurate measurement. Refer to instruction manual for details.

\* Specification subject to change without notice

**TOKYO KEISO CO., LTD.**

Head Office : Shiba Toho Building, 1-7-24 Shibakoen, Minato-ku, Tokyo 105-8558

Tel : 03-3431-1625 (KEY) ; Fax : 03-3433-4922

e-mail : overseas.sales@tokyokeiso.co.jp ; URL : http://www.tokyokeiso.co.jp

ISO 9001 Certified  
JQA-2172